

(e) Notwithstanding any provision to the contrary, the Department of Inspections and Permits may reduce the required setback where (1) the necessity for the setback may be eliminated or reduced by the construction of retaining walls, or (2) if the Owner has a letter of authorization to extend slopes onto the adjacent property.

#### Section 12-2031. DRAINAGE.

Surface water RUNOFF may be ~~run-off~~ DISPOSED OF OR CONVEYED in accordance with the following provisions:

(1) Drainage facilities shall be designed to prevent erosion, overflow or ponding. Said water shall be conveyed to an acceptable outlet in accordance with the design criteria, standards and procedures required by the Public Works Department. The ponding of water shall not be permitted above cut or fill slopes or on drainage terraces; adequate drainage facilities shall be provided to prevent such ponding.

(2) Surface and/or ground waters shall not damage the face of any cut or fill; slopes shall be protected from surface water runoff by berms, swales, or brow ditches. Suitable underdrains shall be installed to intercept and carry ground water seepage to an acceptable outlet.

(3) All areas shall be graded to provide for positive drainage away from the building toward the approved disposal area.

(4) Retention and infiltration subject to the requirements and recommendation of the Anne Arundel Soil Conservation District and the Department of Water Resources. Measures such as infiltration beds, dry wells, and retention ponds may be used to allow storm water runoff to percolate into the soil.

#### Section 12-2032. INSPECTION PROCEDURES.

Prior to initiating any operations subject to this Subtitle, the permittee shall submit to the Department of Inspections and Permits for its approval, a proposed inspection and construction control program.

#### Section 12-2033. NOTIFICATION TO INSPECT.

(a) After commencing initial grading operations, the permittee shall request inspections by the Department of Inspections and Permits at the following stages in the development of the site, or of each subdivision thereof AS SET FORTH IN THE PLANS AND SPECIFICATIONS:

(1) Upon completion of stripping, the stockpiling of top soil, the construction of temporary erosion control facilities and, disposal of all unsuitable materials; ~~but prior to beginning any other~~ AND preparation of the ground TO RECEIVE FILL; BUT PRIOR TO BEGINNING ANY PLACEMENT.