

## 5th Division, 14 miles 680 yards.

85,792 cubic yards excavation and embankment,	14,907 64	
Clearing and grubbing,	798 00	
Bridges and culverts,	14,880 00	
Superstructure,	55,720 09	
	<hr/>	86,305 73

## 6th Division, 18 miles 1653 yards.

79,129 cubic yards excavation and embankment,	20,367 16	
Clearing and grubbing,	1,060 00	
Bridges and culverts,	8,560 00	
Superstructure,	73,534 70	
	<hr/>	103,521 86

## 7th Division, 9 miles 1437 yards.

205,182 cubic yards excavation and embankment,	60,722 13	
Clearing and grubbing,	530 00	
Bridges and culverts,	16,766 00	
Superstructure,	38,065 88	
	<hr/>	116,084 01

## 8th Division, 17 miles 1163 yards.

392,900 cubic yds embankment,	113,579 47	
Clearing and grubbing,	880 00	
Bridges and culverts,	38,980 00	
Superstructure,	68,523 85	
	<hr/>	221,963 32

Total cost of embankment, excavation, grubbing, bridges, and superstructure as above,	£854,273 77	
Depots, water stations, wharves, and condemnation of land, &c.	91,500 00	
	<hr/>	

Contingencies not included in the preceding items,	945,773 77	
	<hr/>	
		75,004 00